

**MISSISSIPPI WORKSHOP /
THE ALL-WOOD BUILDING**

WAECHTER ARCHITECTURE





Our vision and mission can be summarized in a word—Clarity.

We believe that architecture is at its best when buildings are legible, when they make sense, and when they elegantly serve their purpose.

Clarity isn't just a style or formal vocabulary, it's an experience that yields a feeling of calm, assurance, and limitless possibility.








- 01 PROJECT OVERVIEW**
- 02 CONTEXT**
- 03 PROGRAMMING CONCEPT**
- 04 MATERIAL SYSTEMS**
- 05 CONSTRUCTION SEQUENCING**
- 06 WATERPROOFING AND INSULATION**
- 07 SYSTEMS INTEGRATION**
- 08 CONSTRUCTION DETAILS**
- 09 CODES / FIRE RESISTANCE**
- 10 POST OCCUPANCY ANALYSIS**

PROJECT OVERVIEW












CONTEXT



N BLANDENA STREET

N GOING STREET

I-5 FREEWAY

N MARYLAND AVENUE

N SKIDMORE STREET

N HAIGHT AVENUE

N COMMERCIAL AVENUE

N KERBY AVENUE

N NORTHWICK AVENUE

N ALBINA AVENUE

N MISSISSIPPI AVENUE

N MICHIGAN AVENUE

N MASON STREET

N SHAVER STREET

N MISSOURI AVENUE

N MONTANA AVENUE

N INTERSTATE AVENUE





Portland Archives, A2009-009.1025







ORGANIZATION AND PROGRAMMING CONCEPTS




(TODAY)



 OFFICE


 RESIDENTIAL

 RETAIL / WORKSHOP / EDUCATION



FIRST FLOOR PLAN














WAWA
WARRKS
HCSH
HSHS



WACHTER
WORKSHOP







SECOND FLOOR PLAN




















THIRD FLOOR PLAN







MATERIAL SYSTEMS

GENERAL INFORMATION

CROSS-LAMINATED TIMBER



PRODUCT DESCRIPTION

KLH® CLT is a versatile building material characterized by its dimensional stability and accuracy, and its high level of prefabrication. KLH® solid wood panels are used for wall, floor slab, and roof elements.

The biaxial qualities of CLT provide a multitude of opportunities for exciting architectural designs. KLH® elements can be combined with most building materials and structural systems to produce exciting and innovative design arrangements. By utilizing CLT in a bearing wall system, the thicknesses of floor and wall elements can be minimized to achieve an increase in building volume over traditional framed bearing wall and dropped-ceiling systems.

KLH® superstructures are erected by knowledgeable construction companies, typically using a mobile crane. An average of 25 minutes is required to place each element, depending on the complexity of the structure and site conditions. Erection of CLT for a detached residential dwelling of average size and complexity typically takes approximately 1-2 days. Erection crews are usually made up of four workers and a crane operator, and typical panel-to-panel connections are made with long wood screws and simple tools.

MAXIMUM DIMENSIONS AND PRODUCED WIDTHS

Maximum panel length	54'-2"
Maximum panel width	9'-8"
Maximum panel thickness	1'-8"
Produced widths	7'-10" / 8'-2" / 8'-11" / 9'-8"
Minimum production length	27'-1" – in 2" increments

MANUFACTURE

KLH® solid wood elements are made up of a least 3 layers of lumber boards that are arranged perpendicular to each other and glued together under high pressure. Depending on the project requirements, we can supply PEFC and FSC® C119602 -certified panels on request.

By cross-laminating the lumber boards, swelling and shrinkage are restrained, providing excellent dimensional stability of the finished product. In accordance with ANSI/ APA PRG 320, only kiln dried lumber with a moisture content of 12% (+/- 2%) is used in KLH® CLT.

The fabrication process is subject to internal and external quality control by authorized third party auditors.

ADHESIVES AND LAMINATION PROCESS



PEFC or FSC® C119602 - certified lumber stock is graded and sorted according to grade and surface quality.



Cross-laminated timber is produced on a just-in-time basis



Formaldehyde-free adhesive is used for laminating the individual layers



State-of-the-art CNC cutting machines facilitate both simple and highly complex patterns according to project requirements.

ADHESIVES AND LAMINATION PROCESS


Only VOC-free and formaldehyde-free PUR adhesives are used in accordance with ANSI 405 and CSA 0112.10.

Adhesive is applied automatically over the entire surface at approximately 0.03 lbs/ft² per joint. Combined with a laminating pressure of 87 psi, KLH® CLT is manufactured to consistently high standards of strength and quality.

Furthermore, production takes place in a highly controlled manufacturing environment where temperature and humidity are continuously monitored and consistently maintained, ensuring the specified moisture content of both lumber stock and finished product.

More information about the adhesives used may be found at www.henkel-adhesives.de.

**CARBON EMISSIONS
MATERIAL, SOURCING & TRANSPORT**



Comparison of carbon emissions between timber design and concrete design over lifecycle of structural materials in a 12-story tower.

CARBON LCA

ENVIRONMENTAL PRODUCT DECLARATION

as per /ISO 14025/ and /EN 15804/

Owner of the Declaration	KLH Massivholz GmbH
Programme holder	Institut Bauen und Umwelt e.V. (IBU)
Publisher	Institut Bauen und Umwelt e.V. (IBU)
Declaration number	EPD-KLH-20190027-ICA1-EN
Issue date	06.05.2019
Valid to	05.05.2024

KLH cross-laminated timber panels
KLH Massivholz GmbH




www.ibu-epd.com / <https://epd-online.com>




Project Name / Number	Mississippi	
Date	19/02/2021	
Country of construction	United States	
Volume of KLH® - CLT element	446	[m³]
Transport by Truck	1100	[km]
Ship	9090	[nm]

This project produces a total of (A1-A5)	174.4	tons CO ₂ equ.
This project stores a total of (CO ₂ wood)	-354.1	tons CO ₂ equ.




After Assembly (stage A5) the projects footprint results in a total of	-179.7	tons CO ₂ equ..
Regrow time (in Austrian forests, considering actual sawn timber)	15.3	minutes


All values are based on the KLH® EPD that was verified by external assessment and the data quality was checked before public release. The calculation of the background data is based on the ecoinvent database. All standards and literature are stated in the EDP document, which is available on www.klh.at



Building Parts




Building Whole




- 1 CLT Floor Panels
- 2 CLT Exterior Wall Panels
- 3 CLT Courtyard Exterior Wall Panels
- 4 CLT Interior Wall Panels
- 5 CLT Stair
- 6 Glulam Beams

Building Assembly


FABRICATION SCOPE IMAGE FOR REFERENCE.
SEE ELEVATIONS FOR DETAILED INFORMATION



2 Wall Panel Layup Types
CLT-100 SCALE: N.T.S.



Panel Label



1 CLT Wall Panel Fabrication ISO
CLT-100 SCALE: N.T.S.

QUALITY ASSURANCE:

- STORE PANELS IN CONDITIONED AND HUMIDITY CONTROLLED ENVIRONMENT.
- KLH RECOMMENDS END GRAIN SEALER ON PANEL EDGES TO MINIMIZE MOISTURE ABSORPTION AND PREVENT VISIBLE CAPILLARY ACTION IN WOOD END GRAIN.
- ALL STEEL COMPONENTS SHOULD BE PRIMED, POWDER COATED, OR STAINLESS STEEL.
- DO NOT CUT OR WELD STEEL NEAR PANELS WITHOUT FIRST PROTECTING FROM FERROUS STAINING.
- APPLY MOISTURE (AND INSECT WHERE APPROPRIATE) BARRIER BETWEEN PANEL EDGE AND SILL PLATE.
- SHIM UNDER SILL ELEMENT. DO NOT SHIM DIRECTLY UNDER PANEL.
- REMOVE EXCESS WATER AND MINIMIZE EXPOSURE TIME FOR BEST RESULTS.

PROJECT NOTES:

- VERIFY DETAILS FIT FIELD CONDITIONS AND OTHER CONSTRUCTION SYSTEMS.
- ALL CONNECTIONS ARE APPROXIMATE, AND TO BE REVIEWED AND APPROVED BY STRUCTURAL ENGINEER.
- SPRUCE SPLINE BOARD MATERIAL TO BE PROVIDED BY KLH.
- FASTENERS AS NOTED ON S-7.1 / S-7.2 / S-7.5 / S-7.6 TO BE PROVIDED BY KLH.
- RICON CONNECTORS FOR GLULAMS TO BE PROVIDED BY KLH.
- ALL OTHER STEEL CONNECTIONS TO BE PROVIDED BY OTHERS
- STRUCTURAL STEEL TO BE PROVIDED BY OTHERS.

DRAWING NOTES:

1. This drawing is the property of KLH USA Holding. Copyright is reserved & this drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorised person, either wholly or in part, without our consent. Do not scale from this drawing, check all dimensions on site. If in doubt, please ask.
2. All dimensions are shown both in millimeters [inches] unless noted otherwise. The grades of finish are as follows: NSI (non visual quality); ISI (visible industrial quality); WSI (domestic quality).
3. Where not specified, the grade finish would be NSI.
4. The finish to the side facing down is shown with parentheses and the top face is shown without.
5. HH= Head Height; CH=Cill Height; H=Height All Heights refer to Structural Slab Level (SSL)
6. All openings and notches have routed corners (standard radius = 20mm), unless noted or instructed otherwise. Square corners to openings and notches less than 500mm wide will have to be cut on site by installation team.
7. X: Elevation title Y: Section title
XXX: Drawing No. YYY: Drawing No.
8. Installation of KLH super structure to be strictly in accordance with project related OSHA requirements. Please refer to installer for this information.

WET STAMP & DATE:

FABRICATION DRAWING APPROVAL

- | | |
|--|---|
| <input type="checkbox"/> Material Order Approved | <input type="checkbox"/> No Exception Taken |
| <input type="checkbox"/> Approved With Comments | <input type="checkbox"/> Field Notes Required |
| <input type="checkbox"/> Submit Specified Items | <input type="checkbox"/> Not Reviewed |
| <input type="checkbox"/> Revise and Resubmit | <input type="checkbox"/> Rejected |

Signing below releases these fabrication drawings for production. Changes to panel specifications, quantity, or size, delays in approval, or changes after approval may add to the cost and / or cause delay. Approval of these drawings constitutes an understanding that all other drawings are superseded by these drawings with regard to the delivered CLT scope.

Approved by: _____
Date: _____




240 N Broadway
Suite 308
Portland, OR 97212
T: 1 971.998.5705
E: michael.hahn@klhusa.com

REV	DESCRIPTION	DATE	BY	CHK
3	Third Issue	06.16.2020	MH	-
2	Grid E Release	06.08.2020	MH	WA
1	Second Issue	05.26.2020	MH	WA
0	First Issue	05.13.2020	MH	WA


PROJECT
USA_245-E
Waechter - Mississippi Wall E
4236 N Mississippi Ave.
Portland, OR 97217

DRAWING TITLE
CLT Wall Panel
Fabrication ISO


STATUS GRID E RELEASE	SCALE AS NOTED
DRAWING NO. CLT-100	REV. 3



2 Project Panel Layup Types
CLT-101 SCALE: N.T.S.



FABRICATION SCOPE IMAGE FOR REFERENCE.
SEE PLANS FOR DETAILED INFORMATION



1 CLT Floor Panel Fabrication ISO
CLT-101 SCALE: N.T.S.

DRAWING NOTES:

- This drawing is the property of KLH USA Holding. Copyright is reserved & this drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorized person, either wholly or in part, without our consent. Do not scale from this drawing, check all dimensions on site. If in doubt, please ask.
- All dimensions are shown both in millimeters [inches] unless noted otherwise. The grades of finish are as follows: NSI (non visual quality); ISI (visible industrial quality); WSI (domestic quality).
- Where not specified, the grade finish would be NSI.
- The finish to the side facing down is shown with parentheses and the top face is shown without.
- HH= Head Height; CH=Cill Height; H=Height All Heights refer to Structural Slab Level (SSL)
- All openings and notches have routed corners (standard radius = 20mm), unless noted or instructed otherwise. Square corners to openings and notches less than 500mm wide will have to be cut on site by installation team.
- X: Elevation title Y: Section title
 XXX: Drawing No. YYY: Drawing No.
- Installation of KLH super structure to be strictly in accordance with project related OSHA requirements. Please refer to installer for this information.

WET STAMP & DATE:

FABRICATION DRAWING APPROVAL

<input type="checkbox"/> Material Order Approved	<input type="checkbox"/> No Exception Taken
<input type="checkbox"/> Approved With Comments	<input type="checkbox"/> Field Notes Required
<input type="checkbox"/> Submit Specified Items	<input type="checkbox"/> Not Reviewed
<input type="checkbox"/> Revise and Resubmit	<input type="checkbox"/> Rejected

Signing below releases these fabrication drawings for production. Changes to panel specifications, quantity, or size, delays in approval, or changes after approval may add to the cost and / or cause delay. Approval of these drawings constitutes an understanding that all other drawings are superseded by these drawings with regard to the delivered CLT scope.

Approved by: _____
 Date: _____

KLH
 240 N Broadway
 Suite 308
 Portland, OR 97212
 T: 1 971.998.5705
 E: michael.hahn@klhusa.com


REV	DESCRIPTION	DATE	BY	CHK
3	Third Issue	06.16.2020	MH	-
2	Grid E Release	06.08.2020	MH	WA
1	Second Issue	05.26.2020	MH	WA
0	First Issue	05.13.2020	MH	WA

PROJECT
USA_245-E
Waechter - Mississippi Wall E
 4236 N Mississippi Ave.
 Portland, OR 97217


DRAWING TITLE
CLT Floor Panel Fabrication ISO

STATUS GRID E RELEASE	SCALE AS NOTED
DRAWING NO. CLT-101	REV. 3

SHOP DRAWING MODEL







ABUS 15t (8t/8t) AST



RR

KLH



MAERSK

VB 1011T

D-TEC


CONSTRUCTION SEQUENCING


















































PPL
Loc
←


























**WATERPROOFING
& INSULATION**

























SYSTEMS INTEGRATION
















**CONSTRUCTION
DETAILS**

TYPICAL CLT CONNECTION TO STEM WALLS



NOTES:




1. REF. ARCH. FOR L6x6 LOCATIONS AT INSIDE / OUTSIDE FACE.
2. REF. S5.3 FOR FOOTING AND CURB INFORMATION.

TYP. CLT SHEAR WALL TO CONCRETE CONNECTION


1 1/2" = 1'-0"

2



Courtesy KPFF Engineering



TYPICAL CLT CONNECTION TO STEM WALLS





OUTSIDE CORNER HOLD DOWN




5 HOLDDOWN AT GRID E
 1 1/2" = 1'-0"

TYP CLT TO PIER



1 TYP. CLT PIER TO CONC. CURB/FDN.
1 1/2" = 1'-0"

CLT VERTICAL SPLICE





CLT SHEAR WALL VERTICAL PANEL SPLICE DETAIL


1

1 1/2" = 1'-0"

Courtesy KPFF Engineering



TYP GLULAM BEAM TO CLT WALL CONNECTION





- NOTES:**
1. REF. 6/S7.1 FOR INFORMATION NOT SHOWN. △1
 2. SIMPSON STRAPS NOT SHOWN FOR CLARITY. THE CONNECTOR SCREWS AND STRAP NAILS SHALL BE LOCATED PRIOR TO ERECTION TO AVOID CONFLICTS.

TYPICAL GLULAM BEAM TO CLT WALL CONNECTION


8


1 1/2" = 1'-0"

Courtesy KPFF Engineering




TYP GLULAM BEAM TO CLT WALL CONNECTION






CLT / GLULAM STAIR




5 Project Panel Layup Types

CLT-104 SCALE: N.T.S.




Panel Label




4 Enlarged Typical Assembly ISO

CLT-104 SCALE: N.T.S.




3 Glulam Treads & CLT Stringers

CLT-104 SCALE: 1/2" = 1'-0"



2 CLT Guardrails

CLT-104 SCALE: 1/2" = 1'-0"




1 CLT Landings & Steel Ledgers


CLT-104 SCALE: 1/2" = 1'-0"

STAIR SCOPE DESIGN PACKAGE.
DEFERRED SUBMITTAL

CLT / GLULAM STAIR




CLT / GLULAM STAIR



**CODES AND
FIRE RESISTANCE**

CODE REVISIONS / FIRE RESISTANCE



FIRST FLOOR PLAN

**HALF-LAP CONDITION
DETAIL 4/A8.2**


**T-JOINT
DETAIL 5/A8.2**

FIRE RATING AND OCCUPANCY SEPARATION


**WALL FULL HEIGHT TO STRUCTURE,
1 HR FIRE BARRIER WITH 45 MIN OPENING PROTECTION**

**FIRE RATED EXTERIOR WALL
1 HR SEPERATION WITH 45 MIN OPENING PROTECTION WITH UNPROTECTED OPENINGS**

CODE REVISIONS / FIRE RESISTANCE



SECOND FLOOR PLAN

 **HALF-LAP CONDITION**
DETAIL 4/A8.2


 **T-JOINT**
DETAIL 5/A8.2

FIRE RATING AND OCCUPANCY SEPARATION

 WALL FULL HEIGHT TO STRUCTURE,
1 HR FIRE BARRIER WITH 45 MIN OPENING PROTECTION


 FIRE RATED EXTERIOR WALL
1 HR SEPERATION WITH 45 MIN OPENING PROTECTION WITH UNPROTECTED OPENINGS

CODE REVISIONS / FIRE RESISTANCE




Not required to satisfy performance requirements of assembly tested in accordance with ASTM E119.

4 CLT SHEAR WALL VERTICAL SPLICE DETAIL
1 1/2" = 1'-0" NOTE: REFER TO DETAIL 1/S7.5 IN STRUCTURAL SET





5 TYPICAL CLT SHEAR WALL T-JOINT
1 1/2" = 1'-0" NOTE: REFER TO DETAIL 3/S7.5 IN STRUCTURAL SET




CODE REVISIONS / FIRE RESISTANCE

Table 4.1.1.4B Effective Char Depth (for CLT with $\beta_n=1.5$ inches/hour)


Required Fire Resistance (hr)	Lamination Thickness, h_{lam} (in.)								
	5/8	3/4	7/8	1	1-1/4	1-3/8	1-1/2	1-3/4	2
	Char Depth, a_{char} (in.)								
1-Hour	1.8	1.8	1.7	1.7	1.7	1.6	1.5	1.5	1.5
1½-Hour	2.8	2.7	2.6	2.5	2.4	2.4	2.4	2.3	2.2
2-Hour	3.7	3.6	3.4	3.4	3.2	3.2	3.0	3.0	3.0
	Effective Char Depth, a_{eff} (in.)								
1-Hour	2.2	2.2	2.1	2.0	2.0	1.9	1.8	1.8	1.8
1½-Hour	3.4	3.2	3.1	3.0	2.9	2.8	2.8	2.8	2.6
2-Hour	4.4	4.3	4.1	4.0	3.9	3.8	3.6	3.6	3.6



a) Structural resistance




b) Integrity






c) Insulation

Figure 1
Fire resistance criteria per ASTM E119



**POST OCCUPANCY ANALYSIS /
USDA WOOD INNOVATION GRANT**










Ledger Connection






Ricon Beam Connection









Drag Plate Connection




Stemwall U-Bracket








WOOD INNOVATION GRANT — ACOUSTIC TESTING



WOOD INNOVATION GRANT — ACOUSTIC TESTING



Results

Acoustics (Airborne and Impact Testing)

Note: Higher dB levels on the above table indicate greater resistance to sound transmission.



While less insulating than typical construction methods overall, the third floor residential spaces approach IBC multifamily standards as well as GSA standards for offices, with the best performing spaces reaching “High-Isolation Office” levels.

Key Takeaway: the 5-ply CLT decking with 1” Piteq acoustic mat used for the 300 level is quieter and compliant with a wider range of performance standards.

Our observation is that furnished and occupied spaces perform significantly better, and we’ve received favorable reports from our tenants for the audibility of speakers and instructors in our ground floor tenant spaces.



WOOD INNOVATION GRANT — THERMAL IMAGING





WOOD INNOVATION GRANT — THERMAL IMAGING




WOOD INNOVATION GRANT — THERMAL IMAGING



WOOD INNOVATION GRANT — INFILTRATION / BLOWER DOOR



WOOD INNOVATION GRANT — INFILTRATION / BLOWER DOOR




Results

Temperature

All spaces remained within a consistent comfort band, indicating proper functioning of the HVAC system.

During the shoulder season, indoor temperatures deviate, suggesting operation of windows with natural ventilation during these periods.

Office Conference Shop Outdoor Daily High Outdoor Daily Average Outdoor Daily Low




Results

Relative Humidity

The ideal range of indoor RH for human health is 40%-60%. During the winter, the indoor RH is frequently below 40%, suggesting **supplemental humidification would be beneficial during the heating season.**

During the shoulder season, indoor RH is within the ideal range and more closely tracks outdoor daily averages.





Results

CO₂

The office/conference spaces have spikes in clusters of five with gaps in between suggesting a workweek occupancy. Levels are typically below 1000 ppm, **indicating adequate ventilation for indoor air quality.**

During the shoulder season, indoor CO₂ levels approach outdoor levels, suggesting the use of natural ventilation.



Results

Formaldehyde / VOC

Formaldehyde was not detected in the indoor air. It is one of the most measurable VOCs and is a good indicator of indoor air quality.

The spent collection tubes on have no color change, indicating no formaldehyde during the test period. While some wood products contain these compounds, the use of PUR (polyurethane resin) for all CLT and Glulam adhesive is likely responsible for the positive result.

Comparative Analysis

One of the objectives of Mississippi’s design was to illustrate the ecological benefit and the economic and logistical feasibility of an “All-Wood” approach. We began with a hypothetical Type 5B building, of similar size, configuration, type and location—i.e. a 10,000sf, three-story, mixed-use building on an urban site in Portland.

We compared conventional stick frame construction, a concrete frame strategy, “Hybrid” construction using CLT frame and decking with standard infill, and two “All-Wood” models: the all-CLT approach used on Mississippi Workshop, and a model utilizing mass plywood panels (MPP).

- **All-Wood (CLT)** **- 124,126** **kgCO2**
- **All-Wood (MPP)** **- 52,440** **kgCO2**
- **Wood Framed** **+ 88,133** **kgCO2**
- **Hybrid CLT** **+ 92,597** **kgCO2**
- **Steel Framed** **+ 284,088** **kgCO2**
- **Concrete Frame** **+ 496,970** **kgCO2**

All-Wood Cross Laminated Timber Building

The All-Wood Cross Laminated Timber building is based entirely off of the Mississippi Project and can be considered an “as-built” analysis of it’s materials.

CO2 Released through building materials: 130,133 (kgCO2)

CO2 Sequestered through wood material used: 42,000 (kgCO2)

Total Carbon Impact:

- 124,126 (kgCO2)

Standard Wood Stud Building

Using the same footprint and volume as the Mississippi Project, an alternate construction system assumes standard wood stud assemblies wrapped in gypsum.

CO2 Released through building materials: 130,133 (kgCO2)

CO2 Sequestered through wood material used: 42,000 (kgCO2)

Total Carbon Impact:


+ 88,133 (kgCO2)

Comparative Analysis

We worked in consultation with KLH, KPFF Structural Engineers and R&H Construction to account for variables in the sequencing and estimated duration for each construction method, again using a building of comparable size, configuration, type and location.

The durations were estimated as follows:

- Hybrid CLT 40 weeks
- Wood Framed 42 weeks 5% increase
- Steel Framed 42 weeks 5% increase
- All-Wood (CLT) 44 weeks 10% increase
- All-Wood (MPP) 44 weeks 10% increase
- Concrete Frame 48 weeks 20% increase



Comparative Analysis

Completed in 2022, Mississippi cost approximately \$3.75 million for 9,550sf (net), plus 1200sf of landscaped courtyard and passageway.

Despite the application of many new systems and materials, the building was delivered for **\$392 per-square-foot**.

We're working with KLH, KPFF Structural Engineers and R&H Construction to estimate material quantities, labor costs, duration, and other key considerations to develop a ROM cost assessment of each construction method.

Given the limited palette of materials, finishes, and other efficiencies, we are seeing that All-Wood construction can be competitive, if not more cost effective, than other approaches.

MATERIAL	Building Design (Cubic Yard, UNO)					
	CLT BUILDING	MPP	HYBRID - MT	WOOD STUD	METAL STUD	CONCRETE
FOUNDATION						
CONCRETE - FOUNDATION	95.44	62.04	62.04	62.04	47.72	85.90
CONCRETE - STEM WALLS	152.03	152.03	152.03	152.03	152.03	X
WALLS						
CLT	358.83	X	26.35	X	X	X
MASS PLYWOOD	X	358.83	X	X	X	X
METAL SIDING (per LBS)	244.35	244.35	244.35	244.35	244.35	244.35
EXT. INSULATION - MINERAL WOOL (per Sqft)	15,714.00	15,714.00	15,714.00	15,714.00	15,714.00	15,714.00
INT. INSULATION - FIBERGLASS (per Sqft)	X	X	1,692.88	1,692.88	1,692.88	X
PLYWOOD (OSB)	X	X	37.40	37.40	37.40	X
GYPSUM BOARD TYPE X - 5/8" (per Sqft)	X	X	19,416.00	19,416.00	19,416.00	X
PAINT (per LBS)	X	X	55.47	55.47	55.47	X
DIMENSIONAL LUMBER	X	X	65.22	65.22	X	X
METAL STUD (per LBS)	X	X	X	X	21,255.46	X
STEEL (per LBS)	X	X	X	X	16,761.60	X
CONCRETE - WALLS	X	X	X	X	X	780.53
FLOOR / CEILING						
CLT	94.57	X	94.57	X	X	X
MASS PLYWOOD	X	94.57	X	X	X	X
CLT BEAMS	50.47	50.47	50.47	X	X	X
CONCRETE	119.59	119.59	119.59	119.59	358.78	717.56
WOOD I-JOIST (per ft)	X	X	X	2,784.00	X	X
LSL	X	X	X	7.00	X	X
METAL DECKING (per LBS)	X	X	X	X	18,952.42	18,952.42
PLYWOOD (OSB)	X	X	25.46	25.46	X	X
INSULATION (per Sqft)	X	X	3,744.47	3,744.47	3,744.47	X
PAINT (per LBS)	X	X	4.49	4.49	4.49	X
STEEL (per LBS)	0.14	0.14	0.14	0.14	43,485.30	X
GYPSUM CEILING BOARD - 5/8" (per Sqft)	X	X	1,571.18	1,571.18	1,571.18	X
ROOF						
ROOF ASPHALT (per ft)	2,858.46	2,858.46	2,858.46	2,858.46	2,858.46	2,858.46
ROOF INSULATION (per ft)	6,052.00	6,052.00	6,052.00	6,052.00	6,052.00	6,052.00
CONCRETE	5.64	5.64	5.64	5.64	16.93	X
MASS PLYWOOD	X	36.51	X	X	X	X
CLT	36.51	X	36.51	X	X	X

Initial quantity survey / material comparison (2023)

THANK YOU!